

NO-4143 452


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
MILLER POND DAM (CT 0..(U) CORPS OF ENGINEERS WALTHAM
NA NEW ENGLAND DIV AUG 80

1/1

UNCLASSIFIED

F/O 13/13


NL



END

FILMED

DEC




MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

PHOTOGRAPH THIS SHEET

AD-A143 452

DTIC ACCESSION NUMBER



LEVEL



INVENTORY

Miller Pond Dam
CT 00154

DOCUMENT IDENTIFICATION

Aug. '80


DISTRIBUTION STATEMENT A

Approved for public release;
Distribution Unlimited

DISTRIBUTION STATEMENT

| | |
|--------------------|---|
| ACCESSION FOR | |
| NTIS | GRA&I <input checked="" type="checkbox"/> |
| DTIC | TAB <input type="checkbox"/> |
| UNANNOUNCED | <input type="checkbox"/> |
| JUSTIFICATION | |
| | |
| | |
| BY | |
| DISTRIBUTION / | |
| AVAILABILITY CODES | |
| DIST | AVAIL AND/OR SPECIAL |
| A/1 | |

DISTRIBUTION STAMP



DATE ACCESSIONED

84 07 26 072

DATE RECEIVED IN DTIC

PHOTOGRAPH THIS SHEET AND RETURN TO DTIC-DDA-2

AD-A143 452

THAMES RIVER BASIN

WATERFORD, CONNECTICUT


MILLER POND DAM
00154

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

AUGUST 1980



THAMES RIVER BASIN

WATERFORD, CONNECTICUT

MILLER POND DAM
00154

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

AUGUST 1980

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

| REPORT DOCUMENTATION PAGE | | READ INSTRUCTIONS BEFORE COMPLETING FORM |
|--|-----------------------|---|
| 1. REPORT NUMBER CT 00154 | 2. GOVT ACCESSION NO. | 3. RECIPIENT'S CATALOG NUMBER |
| 4. TITLE (and Subtitle) Miller Pond Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS | | 5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT |
| 7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION | | 6. PERFORMING ORG. REPORT NUMBER |
| 9. PERFORMING ORGANIZATION NAME AND ADDRESS | | 8. CONTRACT OR GRANT NUMBER(s) |
| 11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254 | | 10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS |
| 14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) | | 12. REPORT DATE August 1980 |
| | | 13. NUMBER OF PAGES 55 |
| | | 15. SECURITY CLASS. (of this report) UNCLASSIFIED |
| | | 15a. DECLASSIFICATION/DOWNGRADING SCHEDULE |
| 16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED | | |
| 17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) | | |
| 18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report. | | |
| 19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Thames River Basin Waterford, Conn. | | |
| 20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dam has total length of approximately 425 ft. and consists of an embankment section with upstream and downstream masonry faces and a masonry spillway section. The dam is 19.5 ft. in height. Based upon the visual inspection at the site and past performance, the project is judged to be in poor condition. Miller Pond Dam is classified as a high hazard, small size dam. The test flood range to be considered is from one-half to full PMF. | | |

BRIEF ASSESSMENT

PHASE I INSPECTION REPORT

NATIONAL PROGRAM OF INSPECTION OF DAMS

| | |
|---------------------|--|
| Name of Dam: | MILLER POND DAM |
| Inventory Number: | CT 00154 |
| State Located: | CONNECTICUT |
| County Located: | NEW LONDON |
| Town Located: | WATERFORD |
| Stream: | HUNTS BROOK |
| Owner: | HERBERT SCHACHT |
| Date of Inspection: | MARCH 20, 1980 |
| Inspection Team: | PETER HEYNEN, P.E. MURALI ATLURU, P.E. MIRON PETROVSKY THEODORE STEVENS |


The dam, built in the 1870's, has a total length of approximately 425 feet and consists of an embankment section with upstream and downstream masonry faces and a masonry spillway section (See Sheet B-1). The top of the embankment section, at elevation 83.5+, varies in width from approximately 14 to 40 feet and is 3.5 feet above the spillway crest. The dam is 19.5 feet in height above the old streambed of Hunts Brook and, with the pond level to the top of the dam, impounds approximately 700 acre-feet of water. The spillway is an 87.8 foot long broad-crested weir located at the right end of the dam and is founded on bedrock. A 4' x 4.5' masonry high-level outlet culvert through the spillway section, at invert elevation 74.0+, is located near the right abutment of the spillway. A 2'x3' masonry low-level outlet culvert, at invert elevation 64.0+, is located in the earthfill section of the dam.


Based upon the visual inspection at the site and past performance, the project is judged to be in poor condition. There are areas which require monitoring and/or maintenance such as: seepage at several locations on the downstream face and toe of the dam, seepage of the low-level outlet culvert, the inoperable low-level outlet gate, eroded areas on the top of the dam, deteriorated masonry at several locations on the dam, and possible erosion or undermining due to high velocity flows along the downstream toe of the spillway and dam.

In accordance with the Army Corps of Engineers' Guidelines, Miller Pond Dam is classified as a high hazard, small size dam. The test flood range to be considered is from one-half to full Probable Maximum Flood (PMF). The test flood for Miller Pond Dam is equivalent to the $\frac{1}{2}$ PMF. Peak inflow to the reservoir at the $\frac{1}{2}$ PMF is 8,610 cubic feet per second (cfs); peak outflow is 7,730 cfs with the dam overtopped by 2.7 feet. The spillway capacity with the reservoir level to the top of the dam is 1,610 cfs, which is equivalent to 21% of the routed test flood outflow.


It is recommended that the owner retain the services of a registered professional engineer to perform a more detailed hydraulic analysis of the adequacy of the existing project discharge. Other items of importance are grading of the top of the dam to eliminate eroded areas, repair of the low-level outlet gate, repair of deteriorated masonry, inspection of the toe of the spillway and dam during no flow conditions and determination of the significance of all seepage. Recommendations made by the engineer should be implemented by the owner.

The above recommendations and further remedial measures presented in Section 7 should be instituted within one year of the owner's receipt of this report.


Peter M. Heynen
Project Manager - Geotechnical
Cahn Engineers, Inc.




C. Michael Horton
Department Head
Cahn Engineers, Inc.



This Phase I Inspection Report on Miller Pond Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and are hereby submitted for approval.

ARAMAST MAHTESIAN, Member
Geotechnical Engineering Branch
Engineering Division

CARNEY M. TERZIAN, Member
Design Branch
Engineering Division

RICHARD DIBUONO, Chairman
Water Control Branch
Engineering Division

APPROVAL RECOMMENDED:

JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspection. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam would necessarily represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions will be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

The Phase I Investigation does not include an assessment of the need for fences, gates, no-trespassing signs, repairs to existing fences and railings and other items which may be needed to minimize trespass and provide greater security for the facility and safety to the public. An evaluation of the project for compliance with OSHA rules and regulations is also excluded.

TABLE OF CONTENTS

| | <u>Page</u> |
|-----------------------------|-------------|
| Letter of Transmittal | |
| Brief Assessment | i, ii |
| Review Board Signature Page | iii |
| Preface | iv |
| Table of Contents | v-vii |
| Overview Photo | viii |
| Location Map | ix |

SECTION 1: PROJECT INFORMATION

| | | |
|-----|---|-----|
| 1.1 | <u>General</u> | 1-1 |
| | a. Authority | |
| | b. Purpose of Inspection Program | |
| | c. Scope of Inspection Program | |
| 1.2 | <u>Description of Project</u> | 1-2 |
| | a. Location | |
| | b. Description of Dam and Appurtenances | |
| | c. Size Classification | |
| | d. Hazard Classification | |
| | e. Ownership | |
| | f. Operator | |
| | g. Purpose of Dam | |
| | h. Design and Construction History | |
| | i. Normal Operational Procedures | |
| 1.3 | <u>Pertinent Data</u> | 1-3 |
| | a. Drainage Area | |
| | b. Discharge at Damsite | |
| | c. Elevations | |
| | d. Reservoir Length | |
| | e. Reservoir Storage | |
| | f. Reservoir Surface | |
| | g. Dam | |
| | h. Diversion and Regulating Tunnel | |
| | i. Spillway | |
| | j. Regulating Outlets | |

SECTION 2: ENGINEERING DATA

| | | |
|-----|--------------------------------|-----|
| 2.1 | <u>Design Data</u> | 2-1 |
| 2.2 | <u>Construction Data</u> | 2-1 |
| 2.3 | <u>Operations Data</u> | 2-1 |

| | | |
|---|---|-----|
| 2.4 | <u>Evaluation of Data</u> | 2-1 |
| | a. Availability | |
| | b. Adequacy | |
| | c. Validity | |
| SECTION 3: VISUAL INSPECTION | | |
| 3.1 | <u>Findings</u> | 3-1 |
| | a. General | |
| | b. Dam | |
| | d. Appurtenant Structures | |
| | d. Reservoir Area | |
| | e. Downstream Channel | |
| 3.2 | <u>Evaluation</u> | 3-2 |
| SECTION 4: OPERATIONAL AND MAINTENANCE PROCEDURES | | |
| 4.1 | <u>Operational Procedures</u> | 4-1 |
| | a. General | |
| | b. Description of Any Warning System in Effect | |
| 4.2 | <u>Maintenance Procedures</u> | 4-1 |
| | a. General | |
| | b. Operating Facilities | |
| 4.3 | <u>Evaluation</u> | 4-1 |
| SECTION 5: EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES | | |
| 5.1 | <u>General</u> | 5-1 |
| 5.2 | <u>Design Data</u> | 5-1 |
| 5.3 | <u>Experience Data</u> | 5-1 |
| 5.4 | <u>Visual Observations</u> | 5-1 |
| 5.5 | <u>Test Flood Analysis</u> | 5-1 |
| 5.6 | <u>Dam Failure Analysis</u> | 5-2 |
| SECTION 6: <u>EVALUATION OF STRUCTURAL STABILITY</u> | | |
| 6.1 | <u>Visual Observations</u> | 6-1 |
| 6.2 | <u>Design and Construction Data</u> | 6-1 |
| 6.3 | <u>Post Construction Changes</u> | 6-1 |
| 6.4 | <u>Seismic Stability</u> | 6-1 |

SECTION 7: ASSESSMENT, RECOMMENDATIONS & REMEDIAL MEASURES

| | | |
|-----|---|-----|
| 7.1 | <u>Dam Assessment</u> | 7-1 |
| | a. Condition | |
| | b. Adequacy of Information | |
| | c. Urgency | |
| 7.2 | <u>Recommendations</u> | 7-1 |
| 7.3 | <u>Remedial Measures</u> | 7-2 |
| | a. Operation and Maintenance Procedures | |
| 7.4 | <u>Alternatives</u> | 7-2 |


APPENDICES

| | | |
|-------------|---|-------------|
| | | <u>Pg</u> |
| APPENDIX A: | <u>INSPECTION CHECKLIST</u> | A-1 to A-5 |
| APPENDIX B: | <u>ENGINEERING DATA AND CORRESPONDENCE</u> | |
| | Dam Plan, Profile and Sections | Sheet B-1 |
| | Summary of Data and Correspondence | B-1 |
| | Data and Correspondence | B-2 to B-10 |
| APPENDIX C: | <u>DETAIL PHOTOGRAPHS</u> | |
| | Photograph Location Plan | Sheet C-1 |
| | Photographs | C-1 to C-3 |
| APPENDIX D: | <u>HYDRAULIC/HYDROLOGIC COMPUTATIONS</u> | |
| | Drainage Area Map | Sheet D-1 |
| | Computations | D-1 to D-19 |
| | Preliminary Guidance for Estimating Maximum Probable Discharges | i to viii |
| APPENDIX E: | <u>INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS</u> | E-1 |



OVERVIEW PHOTO
(February, 1980)

| | | | | | |
|---|--|--|--------------------------------|--------------------------|--|
| US ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS. | NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS | | Miller Pond Dam Hunts Brook | Waterford CONNECTICUT | DATE May 1980 CE # 27 785 KA PAGE viii |
|---|--|--|--------------------------------|--------------------------|--|



LOCATION MAP
CONNECTICUT
0 1 2 3 4 5
SCALE IN MILES
PAGE-IX

PHASE I INSPECTION REPORT

MILLER POND DAM

SECTION I - PROJECT INFORMATION

1.1 GENERAL

a. Authority - Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Cahn Engineers, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of Connecticut. Authorization and notice to proceed were issued to Cahn Engineers, Inc. under a letter of April 14, 1980 from William E. Hodgson, Jr. Colonel, Corps of Engineers. Contract No. DACW 33-80-C-0052 has been assigned by the Corps of Engineers for this work.

b. Purpose of Inspection Program - The purposes of the program are to:

1. Perform technical inspection and evaluation of non-federal dams to identify conditions requiring correction in a timely manner by non-federal interests.
2. Encourage and prepare the States to quickly initiate effective dam inspection programs for non-federal dam.
3. To update, verify and complete the National Inventory of Dams.

c. Scope of Inspection Program - The scope of this Phase I inspection report includes:

1. Gathering, reviewing and presenting all available data as can be obtained from the owners, previous owners, the state and other associated parties.
2. A field inspection of the facility detailing the visual condition of the dam, embankments and appurtenant structures.
3. Computations concerning the hydraulics and hydrology of the facility and its relationship to the calculated flood through the existing spillway.
4. An assessment of the condition of the facility and corrective measures required.

It should be noted that this report does not pass judgement on the safety or stability of the dam other than on a visual basis. The inspection is to identify those features of the dam which need corrective action and/or further study.

1.2 DESCRIPTION OF PROJECT

a. Location - The dam is located on Hunt's Brook in a rural area of the Town of Waterford, County of New London, State of Connecticut. The dam is shown on the U.S.G.S. Montville Quadrangle Map having coordinates latitude N41°24.4' and longitude W72°07.9'.

b. Description of Dam and Appurtenances - As shown on Sheet B-1, the 20 foot high dam is a masonry and earthfill gravity structure, probably founded on bedrock for its entire length. The project is approximately 425 feet in length, consisting of an approximately 335 foot long dogleg shaped earthfill section with upstream and downstream vertical masonry faces and an 87.8 foot long masonry spillway. There is a high-level outlet through the spillway section and a low-level outlet through the earthfill and masonry section.

The 87.8 foot long spillway, at the right end of the dam, is a broad-crested masonry weir of trapezoidal cross-section with a shallow, gravelly approach channel and a nearly vertical downstream face. The spillway discharges onto a large expanse of exposed bedrock at the toe of the dam.

The earthfill and masonry section has a maximum height of approximately 19.5 feet and a top elevation 3.5 feet above the spillway crest. It is approximately 14 feet wide near its left end, widening to a maximum of approximately 40 feet near its center.

A metal sluice gate controls flow through a 2'x3' masonry low-level culvert through the embankment; however, there is no mechanism with which to raise the gate. An approximately 4'x4.5' high-level outlet with upstream masonry training walls is located near the right end of the spillway. There is no gate or operating mechanism for this outlet; however, there are slots in the training walls in which stoplogs may be placed.

c. Size Classification - SMALL - The dam impounds 700 acre-feet of water with the lake level to the top of the dam, which is 19.5 feet above the old streambed. According to the U.S. Army Corps of Engineers' Recommended Guidelines, a dam with this storage capacity is classified as small in size.

d. Hazard Classification - HIGH - If the dam were breached, there is potential for loss of more than a few lives and extensive property damage to at least 3 houses approximately 8 feet above the streambed of Hunt's Brook in a rural area off of Bloomingdale Road approximately 3700 feet downstream of the dam. A secondary impact area, where 3 more structures including 2 houses, would be affected by a breach of the dam, is approximately 6,200 feet from the dam (See Sheet D-1).

- e. Ownership - Mr. Herbert Schacht
Hunts Brook Rd.
Waterford, Ct. 06385
Tel.: (203) 443-8074 (Home)
(203) 442-9454 (Office)

The dam was originally built and owned by the Miller family. The Schacht family acquired the property in 1931.

- f. Operator - Mr. Herbert Schacht (See above)

g. Purpose - The wooded area around the pond is used for recreational purposes by the Waterford Country Day School.

h. Design and Construction History - The following information is believed to be accurate, based on the available data and correspondence and an interview with the owner of the dam. The dam was constructed around 1873 to supply water to a downstream factory. There is no record of any alterations or repairs to the dam until 1963, at which time the low-level outlet gate was repaired, trees and brush on the dam and at its base were removed, the masonry faces of the dam were repointed and dead trees were removed from the spillway.

i. Normal Operational Procedures - The low-level outlet for the dam is kept in a closed position and the high-level outlet is kept open. No formal operational procedures exist.

1.3 PERTINENT DATA

a. Drainage Area - The drainage area is 10.5 square miles of relatively undeveloped, rolling terrain.

b. Discharge at Damsite - Discharge is over the spillway, through the high-level outlet in the spillway section and through the low-level outlet in the masonry and earthfill section.

1. Outlet Works (Conduits):

| | |
|--|--|
| 4'x4.5' masonry culvert at invert el. 74.0+ | 240+ cfs (pond level at top of dam) |
|--|--|

| | |
|--|--|
| 2'x3' masonry culvert at invert el. 64.0+ | 200+ cfs (pond level at top of dam) |
|--|--|

| | |
|------------------------------|-----------|
| 2. Maximum flood at damsite: | Not known |
|------------------------------|-----------|

| | |
|--|-----------|
| 3. Ungated spillway capacity at top of dam el. 83.5+: | 1,610 cfs |
|--|-----------|

| | |
|---|-----------|
| 4. Ungated spillway capacity at test flood el. 86.2: | 3,800 cfs |
|---|-----------|

- | | |
|--|-----------|
| 5. Gated spillway capacity at normal pool: | N/A |
| 6. Gated spillway capacity at test flood: | N/A |
| 7. Total spillway capacity at test flood el. 86.2: | 3,800 cfs |
| 8. Total project discharge at top of dam el. 83.5: | 2,050 cfs |
| 9. Total project discharge at test flood el. 86.2: | 7,730 cfs |

c. Elevations (National Geodetic Vertical Datum based on assumed spillway crest elevation of 80.0)

- | | |
|---|----------------------|
| 1. Streambed at toe of dam: | 64.0 ₊ |
| 2. Maximum tailwater: | N/A |
| 3. Upstream portal invert diversion tunnel: | N/A |
| 4. Recreation pool: | N/A |
| 5. Full flood control pool: | N/A |
| 6. Spillway crest (ungated): | 80.0 (assumed datum) |
| 7. Design Surge (Original): | Not known |
| 8. Top of dam: | 83.5 ₊ |
| 9. Test flood surcharge: | 86.2 |

d. Reservoir Length

- | | |
|-------------------------|------------------------|
| 1. Normal pool: | 3,400 ₊ ft. |
| 2. Flood control pool: | N/A |
| 3. Spillway crest pool: | 3,400 ₊ ft. |
| 4. Top of dam pool: | 3,500 ₊ ft. |
| 5. Test flood pool: | 3,600 ₊ ft. |

e. Reservoir Storage

- | | |
|------------------------|---------------------------|
| 1. Normal pool: | 410 ₊ acre-ft. |
| 2. Flood control pool: | N/A |

- | | |
|---|--|
| 3. Spillway crest pool: | 410+ acre-ft. |
| 4. Top of dam pool: | 700+ acre-ft. |
| 5. Test flood pool: | 950+ acre-ft. |
| f. <u>Reservoir Surface</u> | |
| 1. Normal pool: | 77+ acres |
| 2. Flood control pool: | N/A |
| 3. Spillway crest pool: | 77+ acres |
| 4. Top of dam pool: | 90+ acres |
| 5. Test flood pool: | 99+ acres |
| g. <u>Dam</u> | |
| 1. Type: | Masonry and earthfill |
| 2. Length: | 425+ ft. |
| 3. Height: | 19.5+ ft. |
| 4. Top width: | Varies 40+ ft. max. 14+ ft. min. |
| 5. Side slopes: | Vertical (Upstream) Vertical (Downstream) |
| 6. Zoning: | N/A |
| 7. Impervious Core: | Not known |
| 8. Cutoff: | Not known |
| 9. Grout Curtain: | N/A |
| 10. Other: | N/A |
| h. <u>Diversion and Regulatory Tunnel</u> - N/A | |
| i. <u>Spillway</u> | |
| 1. Type: | Broad-crested masonry weir |
| 2. Length of weir: | 87.8 ft. |
| 3. Crest elevation: | 80.0 (assumed datum) |

- | | |
|------------------------|-------------------------------------|
| 4. Gates: | N/A |
| 5. Upstream Channel: | Shallow, gravel bottom |
| 6. Downstream Channel: | Exposed bedrock |
| 7. General: | Downstream face is at slight batter |

j. Regulating Outlets - The outlets are a high-level outlet through the spillway section and a low-level outlet through the masonry and earthfill section.

High-Level Outlet

- | | |
|-----------------------|---------------------|
| 1. Invert: | 74.0 ₊ |
| 2. Size: | 4'x4.5' |
| 3. Description: | Masonry culvert |
| 4. Control mechanism: | None |
| 5. Other: | Slots for stop logs |

Low-Level Outlet

- | | |
|-----------------------|-------------------------|
| 1. Invert: | 64.0 ₊ |
| 2. Size: | 2'x3' |
| 3. Description: | Masonry culvert |
| 4. Control Mechanism: | None in place |
| 5. Other: | Gate in closed position |

SECTION 2: ENGINEERING DATA

2.1 DESIGN DATA

The available data consists of inventory data by the State of Connecticut, correspondence concerning the 1963 repairs to the dam, and drawings of the 1963 repairs by W.A. Morse, Civil Engineer (See Appendix B).

The drawings and correspondence indicate the design features stated previously in this report.

2.2 CONSTRUCTION DATA

The available data consists of an inspection report by B. H. Palmer for the Connecticut Water Resources Commission concerning the 1963 repairs (Page B-6).

2.3 OPERATIONS DATA

Lake level readings are not taken. It is not known if the spillway capacity of the dam has ever been exceeded. No formal operations records are known to exist.

2.4 EVALUATION OF DATA

a. Availability - Available data was provided by the State of Connecticut; Chandler, Palmer and King, Engineers and the owner. The owner made the project available for visual inspection.

b. Adequacy - The limited amount of detailed engineering data available was generally inadequate to perform an in-depth assessment of the dam, therefore, the final assessment of this dam must be based primarily on visual inspection, performance history, hydraulic computations of spillway capacity and hydrologic estimates.

c. Validity - A comparison of record data and visual observations reveals no significant discrepancies in the record data.

SECTION 3: VISUAL INSPECTION

3.1 FINDINGS

a. General - The general condition of the project is poor. The inspection revealed several areas requiring maintenance, repair and monitoring. At the time of the inspection, the pond level was at elevation 77.8, i.e. 5.7 feet below the top of the dam with water flowing through the high-level spillway outlet.

b. Dam

Top of Dam - The top of the embankment is grass covered with a heavy growth of brush and large trees. Towards the right end of the top of the dam, adjacent to the spillway, an eroded area approximately 6 feet by 6 feet and 6 inches in depth was noted (Photo 1). From this area, erosion of the earthfill extends to the spillway along the upstream masonry wall, which is severely damaged and displaced.

Upstream Face - The upstream masonry face of the dam is in fair condition. The northern (left) area of this face is covered by brush and trees growing along the shoreline upstream of the dam. There are open and cracked mortar joints on the masonry face.

Downstream Face - There is extensive seepage and a large wet area near the toe of the downstream face at a distance of approximately 50 feet to the left of the low-level outlet. The seepage was flowing both through the masonry joints and probably from the base of the dam. The general seepage flow rate in this zone was about 30 gallons per minute (gpm), or more, with separate leaks of up to 10 gpm (Photo 3). In this area, many mortar joints were cracked and leached. The toe of the dam is covered by heavy brush and large trees. One wet area was encountered at a higher elevation than the area described above and had a flow rate at about 1 gpm.

Spillway - The masonry spillway crest is in good condition. No visible cracks or deteriorated zones were observed on the crest (Photo 2). Substantial tree growth and wood debris were noted on the upstream slope of the spillway (Photo 4). The downstream face had some cracking in the mortar joints and several seeps, with a total flow of approximately 3 gpm, in the area of the high-level outlet.

No visible deterioration of the almost submerged high-level spillway outlet was noted. The upstream stone training walls of the outlet are damaged, with partially displaced and fallen stones (Photo 5).

The spillway discharge channel is of exposed bedrock and does not have distinct limits. Approximately one-half of the spillway discharge was running along the toe of the spillway and dam with high velocities, and could cause erosion or undermining along the toe.

c. Appurtenant Structures - The sluice gate stem of the low-level outlet culvert through the earthfill masonry dam is broken and the sluice gate, presently in a closed position, is not operable. However, a considerable flow (approximately 30 gpm) through the culvert, was observed at its outlet (Photo 6). Most of the flow observed at the outlet is entering the culvert from the surrounding body of the dam.

d. Reservoir - The area surrounding the pond is generally wooded and undeveloped except for the Connecticut Turnpike which is adjacent to the northwestern shore of the pond.

e. Downstream Channel - The downstream channel is the natural streambed of Hunts Brook.

3.2 EVALUATION

Based upon the visual inspection, the project is assessed as being in poor condition. The following features which could influence the future condition and/or stability of the project were identified.

1. Significant seepage through the foundation and the masonry, accompanied by leaching of the cement mortar joints, could weaken the masonry and create stability problems.
2. Constant high velocity flow through the high-level outlet may be causing erosion of its upstream training walls.
3. The high velocity flow running along the downstream toe of the spillway and the dam could lead to deterioration and undermining of the masonry at the toe.
4. The lack of an operable mechanism for the sluice gate does not permit use of the low-level outlet in emergency situations.
5. The trees growing on the crest and masonry faces of the dam and on the upstream slope of the spillway can cause weakness of the masonry and additional seepage by penetration of tree roots.
6. Seepage from the body of the dam into the low-level outlet culvert could threaten the stability of the dam due to a loss of soil from the body of the embankment.

SECTION 4: OPERATIONAL AND MAINTENANCE PROCEDURES

4.1 OPERATIONAL PROCEDURES

a. General - Lake level readings are not taken and no regulating procedures are followed at the dam.

b. Description of Any Warning System in Effect - No formal warning system is in effect. The owner reports that he is at the dam during large storms and calls local officials if he detects a problem.

4.2 MAINTENANCE PROCEDURES

a. General - There is no formal program of maintenance or inspection of the dam; however, the owner does perform periodic informal inspections.

b. Operating Facilities - No formal program for maintenance of operating facilities is in effect. The low-level outlet gate was last operated in 1963.

4.3 EVALUATION

The operation and maintenance procedures are generally poor. A formal program of operations and maintenance procedures should be implemented, including documentation to provide complete records for future reference. Also, a formal warning system should be developed and implemented within the time frame indicated in Section 7.1c. Remedial operation and maintenance recommendations are presented in Section 7.3.

SECTION 5: EVALUATION HYDRAULIC/HYDROLOGIC FEATURES

5.1 GENERAL

The watershed is 10.5 square miles of mostly wooded rolling terrain and is sparsely developed. The dam is located on Hunts Brook and has an 87.8 ft. long stone masonry spillway to the right. The spillway section has a high-level outlet with invert elevation 74.0 and the dam section has a low-level outlet with invert elevation 64.0. The high-level outlet has no gate and the low-level outlet is inoperable. The storage of the project is estimated to be 410 acre-feet with the pond level at the spillway crest and 700 acre-feet with the pond level at the top of the dam.

5.2 DESIGN DATA

No hydraulic or hydrologic design data or computations could be found for the original construction.

5.3 EXPERIENCE DATA

The maximum discharge at the dam site is not known and no information was found to indicate that there have been any problems (including overtopping) arising at the dam.

5.4 VISUAL OBSERVATIONS

The spillway is founded on rock and the discharge section immediately downstream of the structure has some obstructions such as boulders, brush and a tree; however, these conditions would have very little effect on the hydraulic performance of the dam.

5.5 TEST FLOOD ANALYSIS

Based upon the U.S. Army Corps of Engineers "Preliminary Guidance for Estimating Maximum Probable Discharges" dated March, 1978, the watershed classification (Rolling) and the watershed area of 10.5 square miles, a Probable Maximum Flood (PMF) of 17,200 cubic feet per second (cfs) or 1640 cfs per square mile is estimated at the damsite. In accordance with the size (small) and hazard (high) classification, the range of test floods to be considered is from the $\frac{1}{2}$ PMF to the PMF. Based upon the severity of the downstream hazard, the test flood for Miller Pond Dam is equivalent to the $\frac{1}{2}$ PMF. Assuming the pond level at the spillway crest at the beginning of the test flood, peak inflow is 8,610 cfs; peak outflow is 7,730 cfs with the dam overtopped by 2.7 feet. The spillway capacity to the top of the dam is 1610 cfs which is equivalent to 21% of the routed test flood outflow (Appendix D-10, D-11).

5.6 DAM FAILURE ANALYSIS

The dam failure analysis is based on the April, 1978 Army Corps of Engineers "Rule of Thumb Guidance for Estimating Downstream Dam Failure Hydrographs." With the reservoir level at the top of the dam, peak prefailure outflow would be about 1860 cfs and the peak failure outflow from a breach of the dam would total about 12,000 cfs. Based on an examination of the conditions downstream of the dam, it is assumed that attenuation of the flood volume would be insignificant and hence the peak flow rate at the impact areas is taken as 12,000 cfs in this analysis.

A breach of the dam would result in a rise of 5.2 feet in the water level of the stream at the initial impact area, located 3700 feet downstream of the dam in the vicinity of Bloomingdale Road. This corresponds to an increase in the water level of the stream from a prefailure flow depth of 5.1 feet to a depth of 10.3 feet after failure of the dam. This condition, in conjunction with the culvert constriction, would impact 3 houses. One house, located upstream of the culvert and north of the stream, is approximately 8 feet above the channel bed and its first floor would be flooded with approximately 2.3 feet of water. Two additional houses east of Bloomingdale Road would also be impacted by 2 feet of floodwater. A secondary impact area 6200 feet downstream of the dam in the vicinity of Old Norwich Road would similarly be impacted by breaching of the dam, with flooding of at least 3 buildings, one of which contains several businesses. The rise in the stage of the stream just above the Old Norwich Road is estimated to be 4.8 feet, which corresponds to an increase from a prefailure flow depth of 4.8 feet to a depth of 9.6 after failure of the dam. The building containing businesses is approximately 7 feet above the channel bed and would be flooded with 2.6 feet of water. Also, two houses located east of Old Norwich Road and adjacent to the Brook are likely to be impacted by dam failure. Because a breach of Miller Pond Dam would cause severe economic loss and the loss of more than a few lives, it is classified as a high hazard dam.

SECTION 6: EVALUATION OF STRUCTURAL STABILITY

6.1 VISUAL OBSERVATIONS

The visual inspection did not reveal any indications of immediate stability problems. There are areas of seepage, deterioration, and erosion, as described in Section 3, however they are not considered stability concerns at the present time.

6.2 DESIGN AND CONSTRUCTION DATA

The drawings and data available and listed in Appendix B were not sufficient to perform an in-depth stability analysis of the dam. No engineering assumptions, data or calculations could be found for the original design of the dam.

6.3 POST CONSTRUCTION CHANGES

The post-construction changes of the project include the following data pertaining to the 1963 repairs to the dam.

1. Operating mechanism of the sluice gate of the low-level outlet.
2. Repointing the cement mortar joints of the masonry faces of the dam.

6.4 SEISMIC STABILITY

The project is in Seismic Zone 1 and according to the recommended Guidelines, need not be evaluated for seismic stability.

SECTION 7: ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

7.1 PROJECT ASSESSMENT

a. Condition - Based upon the visual inspection of the site and past performance, the project appears to be in fair condition. No evidence of immediate structural instability was observed in the embankments, spillway and appurtenant structures. However, there are areas which require maintenance, repair and monitoring.

Based upon the Army Corps of Engineers' "Preliminary Guidance for Estimating Maximum Probable Discharges" dated March, 1978, the watershed classification and hydraulic/hydrologic computations, peak inflow to the pond at test flood is 12,000 cubic feet per second (cfs); peak outflow is 12,000 cfs with the dam overtopped 4.7 feet. Based upon our hydraulic computations, the spillway capacity to the top of dam is 1,900 cfs, which is equivalent to approximately 16% of the routed test flood outflow.

b. Adequacy of Information - The information available is such that an assessment of the condition and stability of the project must be based solely on visual inspection, past performance and sound engineering judgement.

c. Urgency - It is recommended that the measures presented in Section 7.2 and 7.3 be implemented within one year of the owner's receipt of this report.

7.2 RECOMMENDATIONS

It is recommended that further studies be made by a registered professional engineer qualified in dam design and inspection pertaining to the following items. Recommendations made by the engineer should be implemented by the owner.

1. A detailed hydraulic analysis of the adequacy of the project discharge and existing outlet facilities, including an evaluation of the outlet culvert through the right section of the dam and the absence of a low-level outlet.
2. An inspection of the inside of the masonry arch culvert and the sluice gate openings through the right embankment of the dam for possible deterioration and an inspection of the outlet canal, its masonry training wall and 12 inch C.I. drain pipe to determine their condition. These inspections can be performed during the annual draining of the canal.
3. An inspection of the masonry spillway and spillway apron when no water is flowing over the spillway. This should include evaluation of seepage through the spillway, possible deterioration of the masonry downstream face of the spillway and possible undermining or erosion conditions at the toe.

6. Determination of the origin and significance of seepage at the downstream face and the toe of the dam and, if necessary, development of a boring program to determine the condition of the masonry of the dam and spillway and foundation conditions.
7. Based upon the findings of item 6, above, a program to monitor or eliminate seepage through the dam, spillway and foundation should be developed.
8. Repair of the leached and open mortar joints on the masonry of the upstream and downstream faces of the dam and spillway.

7.3 REMEDIAL MEASURES

Operation and Maintenance Procedures - The following measures should be undertaken by the owner within the length of time indicated in Section 7.1.c, and continued on a regular basis.

1. Round-the-clock surveillance should be provided during periods of heavy precipitation or high project discharge. A formal downstream warning system should be developed to be used in case of emergencies at the dam.
2. A formal program of operation and maintenance procedures should be instituted and fully documented to provide accurate records for future reference.
3. A comprehensive program of inspection by a registered professional engineer qualified in dam inspection should be instituted on an annual basis.
4. The top of the masonry walls of the dam with displaced and fallen masonry blocks should be reinforced and restored.
5. Eroded areas of the earthfill dam crest should be filled with suitable soils, compacted and seeded.
6. The damaged masonry of the upstream training walls of the high-level outlet should be repaired.
7. The cutting of grass, brush and trees on the crest, faces and at the toe of the dam and spillway should be performed and continued as part of the routine maintenance procedures.

7.4 ALTERNATIVES

This study had identified no practical alternatives to the above recommendations.

APPENDIX A
INSPECTION CHECKLIST

VISUAL INSPECTION CHECK LIST
PARTY ORGANIZATION

PROJECT Miller Pond Dam

DATE: Mar 20, 1980

TIME: 2:00 pm

WEATHER: Sunny, 50°

W.S. ELEV. 77.8 U.S. _____ DN.S

PARTY:

INITIALS:

DISCIPLINE:

| | | |
|-----------------------------|-----------|---------------------|
| 1. <u>Peter Heynen</u> | <u>PH</u> | <u>Geotechnical</u> |
| 2. <u>Miron Petrovsky</u> | <u>MP</u> | <u>Geotechnical</u> |
| 3. <u>Theodore Stevens</u> | <u>TS</u> | <u>Geotechnical</u> |
| 4. <u>Murali Atluru</u> | <u>MA</u> | <u>Hydraulics</u> |
| 5. <u>Moshé Norman</u> | <u>MN</u> | <u>Survey</u> |
| 6. <u>Timothy Kavanaugh</u> | <u>TK</u> | <u>Survey</u> |

PROJECT FEATURE

INSPECTED BY

REMARKS

| | | |
|------------------------------------|-----------------------|----------------------------|
| 1. <u>Earthfill Embankment</u> | <u>PH, MP, TS, MA</u> | <u>Fair Condition</u> |
| 2. <u>Low-level Outlet Culvert</u> | <u>PH, MP, TS, MA</u> | <u>Very Poor Condition</u> |
| 3. <u>High-Level Outlet</u> | <u>PH, MP, TS, MA</u> | <u>Fair Condition</u> |
| 4. <u>Masonry Spillway</u> | <u>PH, MP, TS, MA</u> | <u>Fair Condition</u> |
| 5. _____ | _____ | _____ |
| 6. _____ | _____ | _____ |
| 7. _____ | _____ | _____ |
| 8. _____ | _____ | _____ |
| 9. _____ | _____ | _____ |
| 10. _____ | _____ | _____ |
| 11. _____ | _____ | _____ |
| 12. _____ | _____ | _____ |

PERIODIC INSPECTION CHECK LIST

Page A-2PROJECT Miller Pond DamDATE 3-20-80PROJECT FEATURE Earthfill Embankment BY PH, MP, TS, MA

| AREA EVALUATED | CONDITION |
|---|--|
| <u>DAM EMBANKMENT</u> | |
| Crest Elevation | 83.5± |
| Current Pool Elevation | 77.8± |
| Maximum Impoundment to Date | Not known |
| Surface Cracks | None observed |
| Pavement Condition | Grass covered |
| Movement or Settlement of Crest | Depression on U/s edge near low-level outlet |
| Lateral Movement | } Too irregular to judge |
| Vertical Alignment | |
| Horizontal Alignment | Fair |
| Condition at Abutment and at Concrete Structures | |
| Indications of Movement of Structural Items on Slopes | N/A |
| Trespassing on Slopes | No slopes-trespassing on top |
| Sloughing or Erosion of Slopes or Abutments | None observed |
| Rock Slope Protection-Riprap Failures | N/A |
| Unusual Movement or Cracking at or Near Toes | None observed, but are high velocity flows along toe |
| Unusual Embankment or Downstream Seepage | yes - from area near low-level outlet |
| Piping or Boils | None observed |
| Foundation Drainage Features | N/A |
| Toe Drains | N/A |
| Instrumentation System | N/A |

PERIODIC INSPECTION CHECK LIST

Page A-3PROJECT Miller Pond DamDATE 3-20-80PROJECT FEATURE Low-Level OutletBY PH, MP, TS, MA

| AREA EVALUATED | CONDITION |
|---|---|
| <u>OUTLET WORKS-TRANSITION AND CONDUIT</u> | 2'x3' Masonry Culvert |
| General Condition of Concrete ^{Masonry} | Poor - Heavy Leakage |
| Rust or Staining on Concrete ^{Masonry} | None observed |
| Spalling | N/A |
| Erosion or Cavitation | N/A |
| Cracking | N/A |
| Alignment of Monoliths | N/A |
| Alignment of Joints | N/A |
| Numbering of Monoliths | N/A |
| | Seepage (± 30 gpm) is from body of dam into culvert |
| | Low-level intake submerged- could not observe |

PERIODIC INSPECTION CHECK LIST

Page A-4PROJECT Miller Pond DamDATE 3-20-80PROJECT FEATURE High-Level OutletBY PH, MP, TS, MA

| AREA EVALUATED | CONDITION |
|--|---|
| <u>OUTLET WORKS-INTAKE CHANNEL AND INTAKE STRUCTURE</u> a) <u>Approach Channel</u> Slope Conditions Bottom Conditions Rock Slides or Falls Log Boom Debris Condition of ^{Masonry} Concrete Lining Drains or Weep Holes b) <u>Intake Structure</u> Condition of Concrete - Slots Stop Logs and Slots | High-level outlet at right end of dam in spillway section Flowing at time of inspection Bedrock Approach Channel Shallow slope Bedrock No N/A No Fair, Deterioration of right U/S training wall N/A Poor-cracked, missing Not in place-have not been for several years |



A-4

PERIODIC INSPECTION CHECK LIST


Page A-5PROJECT Miller Pond DamDATE 3-20-80PROJECT FEATURE Masonry SpillwayBY PH, MP, TS, MA

| AREA EVALUATED | CONDITION |
|--|---|
| <u>OUTLET WORKS-SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u> | |
| a) <u>Approach Channel</u> | |
| General Condition | Poor |
| Loose Rock Overhanging Channel | No |
| Trees Overhanging Channel | yes-growing at U/S side of spillway |
| Floor of Approach Channel | Gravel, Sand |
| b) <u>Weir and Training Walls</u> | |
| General Condition of Concrete ^{Masonry} | Left training wall only - right side is rock abutment |
| Rust or Staining | Weir - Good cond. |
| Spalling | Wall - Fair cond. |
| Any Visible Reinforcing | None observed |
| Any Seepage or Efflorescence | N/A |
| Drain Holes | N/A |
| c) <u>Discharge Channel</u> | |
| General Condition | Slight seepage at right end |
| Loose Rock Overhanging Channel | No |
| Trees Overhanging Channel | Non-defined, bedrock |
| Floor of Channel | No |
| Other Obstructions | yes-not a problem |
| | Bedrock |
| | No |

APPENDIX B
ENGINEERING DATA AND CORRESPONDENCE




PLAN



ELEVATION

HORIZONTAL
VERTICAL






NOTES:

1. THIS PLAN WAS COMPILED FROM A CAHN INSPECTION OF THE DAM DATED MAY 1980. DIMENSIONS SHOWN ARE APPROXIMATE NOT TO SCALE AND/OR STRUCTURAL FEATURES ARE NECESSARY FOR CONSTRUCTION.
2. NO ELEVATIONS WERE AVAILABLE FOR THE DAM. THE WATER SURFACE ELEVATION OF 80.0 FC SHOWN ON THE USGS MONTVILLE QUADRA ASSUMED TO BE THE ELEVATION OF THE SPILLWAY. ALL OTHER ELEVATIONS SHOWN ARE REFERRED TO THE ASSUMED SPILLWAY CREST ELEVATION.
3. WATER SURFACE ELEVATIONS, SHORELINE AND CONFIGURATIONS ARE APPROXIMATE, AS OBTAINED FROM DAM INSPECTION ON MARCH 26, 1980.

CORNERS ON DOWNSTREAM MASONRY FACE

| | | | |
|--|---------------------------|--|----------------------------------|
| CAHN ENGINEERS INC. WALLINGFORD, CONNECTICUT ENGINEER | | U.S. ARMY ENGINEER CORPS OF ENGINEERS WALTHAM | |
| NATIONAL PROGRAM OF INSPECTION OF DAMS, ELEVATION & SECTION | | | |
| MILLER POND | | | |
| HUNTS BROOK | | WATER | |
| DRAWN BY H. J. JONES | CHECKED BY T. J. JONES | APPROVED BY [Signature] | SCALE AS SHOWN DATE: MAY 1980 |



NOTES:

1. THIS PLAN WAS COMPILED FROM A CAHN ENGINEERS INSPECTION OF THE DAM DATED MARCH 26, 1980. DIMENSIONS SHOWN ARE APPROXIMATE. NOT ALL TOPOGRAPHIC AND/OR STRUCTURAL FEATURES ARE NECESSARILY IDENTIFIED.
2. NO ELEVATIONS WERE AVAILABLE FOR THE DAM, THEREFORE THE WATER SURFACE ELEVATION OF 80.0 FOR THE POND SHOWN ON THE U.S.G.S. MONTVILLE QUADRANGLE MAP WAS ASSUMED TO BE THE ELEVATION OF THE SPILLWAY CREST. ALL OTHER ELEVATIONS SHOWN ARE REFERENCED TO THE ASSUMED SPILLWAY CREST ELEVATION.
3. WATER SURFACE ELEVATIONS, SHORELINE AND TAILWATER CONFIGURATIONS ARE APPROXIMATE, AS OBTAINED DURING THE DAM INSPECTION ON MARCH 26, 1980.

| | | | |
|---|-------------|---|-----------------------|
| CAHN ENGINEERS INC. WALLINGFORD, CONNECTICUT ENGINEER | | U.S. ARMY ENGINEER DIVISION NEW HAVEN CHIEF OF ENGINEERS WATERWAYS DIVISION | |
| NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS PLAN, ELEVATION & SECTION | | | |
| MILLER POND DAM | | | |
| MOUNTS BROOK | | WATERFORD, CONNECTICUT | |
| DESIGNED BY | CHECKED BY | APPROVED BY | SCALE AS NOTED |
| H. J. JONES | T. J. JONES | [Signature] | DATE MAY 1980 SHEET B |

SUMMARY OF DATA AND CORRESPONDENCE

| <u>DATE</u> | <u>TO</u> | <u>FROM</u> | <u>SUBJECT</u> | <u>PAGE</u> |
|------------------|---|--|---|-------------|
| Sept. 6, 1963 | Cuheca Realty Corp. c/o Mr. Herbert Schacht | William S. Wise Director Connecticut Water Resources Commission | Order to repair dam | B-2 |
| Nov. 22, 1963 | Herbert Schacht | William A. Morse, Civil Engineer | Sketch plans for repair of dam | B-4 |
| Dec. 10, 1963 | William P. Sander Engineer - Geologist Water Resources Commission | Benjamin H. Palmer Chandler & Palmer Engineers | Report on inspection of repairs to dam | B-6 |
| Dec. 20, 1963 | William S. Wise | Herbert Schacht | Progress of repairs dam | B-8 |
| Nov. 19, 1964 | Cuheca Realty Corp. | William S. Wise | Certificate of Approval | B-9 |
| Oct. 24, 1964 | File | Water Resources Commission | Inventory Data | B-10 |



STATE OF CONNECTICUT
WATER RESOURCES COMMISSION
STATE OFFICE BUILDING - HARTFORD 15, CONNECTICUT

September 6, 1963

Cuhoca Realty Corporation
c/o Mr. Herbert Schacht
Waterford Country School
Fire Street, Quaker Hill
Waterford, Connecticut

Gentlemen:

According to the records in this office the so-called Miller's Pond Dam in the Town of Waterford is under your ownership.

Section 25-110 of the 1953 Revision of the General Statutes places under the jurisdiction of this Commission all dams, "which, by breaking away or otherwise, might endanger life or property." The Commission finds that failure of this dam would endanger life or property.

In accordance with Section 25-111 of the General Statutes this dam has been inspected and found to be in an unsafe condition. The statute states in part: . . . "If, after any inspection described herein, the Commission finds any such structure to be in an unsafe condition, it shall order the person, firm or corporation owning or having control thereof to place it in a safe condition or to remove it, and shall fix the time within which such order shall be carried out."

FINDING

Based on the engineer's report covering the inspection of this dam, the Water Resources Commission finds the structure to be in an unsafe condition. It also finds that certain repairs or alterations are necessary to place the structure in a safe condition.

The repairs or alterations to be made should include but are not necessarily limited to the following items:

1. Remove all trees and brush on the dam and at the base of the dam
2. Rebuild entirely the wooden sluice gate
3. Repair the downstream face of the dam
4. Remove dead trees from the present spillway
5. Repair all leaks at the base of the dam

September 6, 1963

ORDER

In accordance with Section 25-111 of the General Statutes you are hereby ordered to make the repairs or alterations necessary to place the structure in a safe category or to remove the structure.


Any repairs or alterations to the structure or its removal shall be carried out in accordance with engineering plans and specifications prepared by a registered engineer and submitted to this Commission for approval and for the issuance of a permit prior to any construction on demolition work in accordance with Section 25-112 of the General Statutes.

The Commission shall be notified within two weeks what steps you plan to take to repair or remove the structure. The work shall be completed within six months of the date of this order.

Very truly yours,

William S. Wise
Director

WSW:dlp



GENERAL PLAN VIEW OF DAM

SCALE: 1" = 40'

1. DAM FACES TO BE POINTED.
2. DEBRIS TO BE REMOVED FROM SPILLWAY.
3. CLAY OF ADEQUATE AMOUNT (DETERMINED BY ENGINEER) TO BE PLACED AT VALVE AREA UPSTREAM.

PLAN AND SECTION VIEWS OF MILLER POND DAM

LOCATED OFF

COLCHESTER ROAD

QUAKER HILL

(WATERFORD) CONNECTICUT


~ HERBERT SCHACHT OWNER

DATE: NOV 22, 1963

W.A. MORSE ~ CIVIL ENGINEER



EXISTING SUPPORT



CHAIN FALL BEING USED TO
RAISE VALVE (PLATE) NOT
LEFT ON JOB AFTER USE.


SECTION A-A OF SHUT OFF ARRANGEMENT

SCALE: 1" = 4'

TWO 8" GALVANIZED STUDS
SET IN LEAD & WALL N/NTS

REMOVABLE 4"x4"x18" OAK STOP


"EYE" TO BE WELDED TO
PLATE PERMITTING PLATE
TO BE RAISED BY CHAIN
FALL.



TWO 30"x4"x4" OAK RUNNERS
WITH 1/2" SLOT FOR SLIDING
GATE. ATTACHED TO WALL
WITH 8" GALVANIZED STUDS
& NUTS, SET IN LEAD

HALL

SECTION B-B OF SHUT OFF ARRANGEMENT



REMOVABLE STOP

December 10, 1963

State of Connecticut
Water Resources Commission
State Office Building
Hartford 15, Connecticut

Re: Miller's Pond

Attention: Mr. William P. Sander
Engineer-Geologist

Dear Sir:

This is in reply to your letter dated December 4 relative to the above project. It is my opinion that a preliminary construction permit be issued on the basis of the plan which was submitted and drawn by W. A. Morse, Civil Engineer dated November 22, 1963.

Please refer to the letter to the Cuheca Realty Corporation dated September 6, 1963 and signed by W. S. Wise, Director. I visited the dam again today and give the following report.

- 1) All trees and brush on the dam and at the base of the dam have been cut and removed.
- 2) The sluice gate, as previously reported, was a metal gate and not a wooden gate. The gate was in satisfactory condition but the gate stem was disconnected. This part of the work has not been done in accordance with the plan referred to above.
- 3) The downstream face of the dam has been repointed in a satisfactory manner.

- 4) The dead trees have been removed from the present spillway.
- 5) The pond is pretty far down because the gate is open so that it is not possible to determine whether all of the leaks at the base of the dam have been stopped. It is my opinion that they are in better condition than at the beginning of the work.

The Contractor, Mr. Brown, told me some weeks ago that he would complete the work on the gate, but as of today it has not been completed.

Very truly yours,

CHANDLER & PALMER

B. H. Palmer

BHP/nir

William S. Wise, Director
Water Resources Commission
State of Connecticut
State Office Building
Hartford 15, Connecticut

Re: Miller's Pond Dam

Dear Mr. Wise:

Thank you for granting us permission to carry out the repairs to the Miller's Pond Dam in accordance with the plans prepared by Mr. W.A. Morse which we submitted to your office.

We have completed the following work: the trees and brush have been removed from the dam and from the base of the dam; the down stream and upstream faces of the dam have been repaired by painting the stone work with cement; the dead trees have been removed from the spillway; fill has been placed against the base of the dam.

We have not completed the rebuilding of the sluice gate and additional clay is to be placed against the base of the dam.

I am writing to you to report the progress made to date and to request a six month extension of the permit to enable us to complete the work in favorable weather. Mr. William Sander of your office advised me this morning over the telephone that a request for an extension must be made to you in writing.

Mr. Benjamin Palmer has advised us before and during all repair work. We are pleased to cooperate with Mr. Palmer in carrying out the recommendations of your commission.

The Browne Construction Co. of Quaker Hill is doing the work.

Mr. Wayne Morse of Quaker Hill is our consulting engineer.

Very truly yours,

Herbert Schacht

HS/s
cc: Mr. B. Palmer
Mr. W. Browne
Mr. W. Morse
 Bd. of Selectmen, Town of Waterford



Vol 155 No 101

STATE OF CONNECTICUT

WATER RESOURCES COMMISSION

STATE OFFICE BUILDING • HARTFORD 15, CONNECTICUT

CERTIFICATE OF APPROVAL

November 19, 1964

Cuheca Realty Corporation
c/o Waterford Country School
Quaker Hill, Connecticut

TOWN: Waterford
RIVER: Hunts Brook
TRIBUTARY:
CODE NO.: T 6.7 HT 2.0

Gentlemen:

NAME AND LOCATION OF STRUCTURE: Millers Pond Dam, located east of Old Colchester Road in the Town of Waterford.

DESCRIPTION OF STRUCTURE AND WORK PERFORMED: Repairs to the dam in accordance with plans prepared by W. A. Morse, dated November 22, 1963.

CONSTRUCTION PERMIT ISSUED UNDER DATE OF: December 13, 1963.

This certifies that the work and construction included in the plans submitted, for the structure described above, has been completed to the satisfaction of this Commission and that this structure is hereby approved in accordance with Section 25-114 of the 1958 Revision of the General Statutes.


The owner is required by law to record this Certificate in the land records of the town or towns in which the structure is located.

WATER RESOURCES COMMISSION

BY: William S. Wise
William S. Wise, Director

class B

APPENDIX C
DETAIL PHOTOGRAPHS



~ MILLER POND ~




PHOTO LOCATION PLAN

MILLER POND DAM

SHEET C-1






Photo 1 - Crest of dam. Note erosion on crest and displacement of masonry on upstream face. (3/20/80).




Photo 2 - Spillway crest and discharge channel. Note high velocity flow along toe of dam (3/20/80).

US ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS

CAHN ENGINEERS INC.
WALLINGFORD, CONN
ENGINEER

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

Miller Pond Dam
Hunts Brook
Waterford, Conn.
CE # 27 785 KA
DATE May '80 PAGE C-1



Photo 3 - One of several seeps located approximately 50 feet to the left of the low-level outlet (3/20/80).



Photo 4 - Upstream slope of spillway (3/20/80).

US ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS

CAHN ENGINEERS INC
WALLINGFORD, CONN
ENGINEER

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

Miller Pond Dam
Hunts Brook
Waterford, Conn.

CE# 27 785 KA
DATE May '80 PAGE C-2



Photo 5 - Deteriorated right training wall of high-level outlet at right end of spillway (3/20/80).




Photo 6 - Downstream end of low-level outlet culvert (3/20/80).

US ARMY ENGINEER DIV NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS


CAHN ENGINEERS INC.
WALLINGFORD, CONN
ENGINEER

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

Miller Pond Dam
Hunts Brook
Waterford, Conn.
CE# 27 785 KA
DATE May '80 PAGE C-3

APPENDIX D
HYDRAULICS/HYDROLOGIC COMPUTATIONS





CAHN ENGINEERS, INC.
WALLINGFORD CONNECTICUT
ENGINEER

U.S. ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASS.

NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS

DRAINAGE AREA MAP

MILLER POND DAM

HUNTS BROOK MONTVILLE, CONNECTICUT

DWN BY: CKD BY: APP BY: SCALE 1"=2000'

APPROXIMATE LIMITS OF
DAM FAILURE
OUTFLOW

MILLER POND
DAM

SECONDARY IMPACT
AREA

INITIAL IMPACT
AREA

USGS QUADRANGLES
MONTVILLE 1970

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-10 SHEET 1 OF 19
NEW ENGLAND DIVISION COMPUTED BY MA DATE 4/22/80
MILLER POND DAM CHECKED BY EL DATE 4/27/80

PROBABLE MAXIMUM FLOOD (PMF) DETERMINATION

DRAINAGE AREA—

THE TOTAL DRAINAGE AREA FOR MILLER POND = 10.5 sq. mi.
 THIS WAS OBTAINED BY ACTUAL MEASUREMENT FROM USGS
 QUADRANGLE MAPS

WATERSHED CLASSIFICATION — "ROLLING"

THIS CLASSIFICATION IS ASSIGNED BY EXAMINING
 THE USGS QUADRANGLE MAPS AND A VISUAL
 OBSERVATION OF SOME OF THE TERRAIN. EVEN THOUGH
 SOME PARTS OF THIS WATERSHED IS "MOUNTAINOUS"
 AND SOME PARTS ARE FAIRLY FLAT, THE MAJORITY
 OF THE WATERSHED IS "ROLLING".

PMF PEAK INFLOW—

FROM CORP. OF ENGINEERS DECEMBER 1977 MAXIMUM PROBABLE
 FLOOD PEAK FLOW RATES GUIDE CURVE FOR A
 DRAINAGE AREA OF 10.5 SQ. MILES,

PEAK FLOW RATE = 1640 CFS/SQ. MILE

∴ PMF PEAK INFLOW = 10.5×1640
 = 17,240 CFS.

SIZE CLASSIFICATION—

FOR THE PURPOSE OF DETERMINING PROJECT SIZE, THE
 MAXIMUM STORAGE ELEVATION IS CONSIDERED
 EQUAL TO THE TOP OF DAM ELEVATION.

TOP OF DAM ELEVATION = 83.5 * NGVD
 ELEVATION OF THE TOP OF DAM AT LOWEST
 POINT 64.0 NGVD

∴ HEIGHT OF DAM 19.5 FEET

* THE WATER SURFACE ELEVATION OF 80 MSL FOR
 THE POND SHOWN ON THE USGS MONTVILLE QUADRANGLE MAP
 (REV. 1970) IS ASSUMED TO BE THE HIGHWAY CREST ELEVATION
 ON NATIONAL GEODEIC VERTICAL DATUM (NGVD) AND ALL OTHER ELEVATIONS
 ARE REFERENCED TO THIS ASSUMED ELEVATION

DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 77-10-17 SHEET 2 OF 19

NEW ENGLAND DIVISION

COMPUTED BY MA

DATE 7/9/80

MILLER POND DAM

CHECKED BY EB

DATE 7/10/80

PLANIMETERING FROM 1952 MAP FOR POND SURFACE AREA
AT EL. 80 = 76.7 ACRES
AT EL. 85 = 95 ACRES (APPROXIMATE)
AT EL. 83.5 (TOP OF DAM) = 81.0 ACRES

A STAGE-POND AREA CURVE IS PLOTTED (SHEET 3)
AVERAGE POND AREA BETWEEN SPILLWAY CREST = 83.1 ACRES
AND TOP OF DAM

1. STORAGE BETWEEN SPILLWAY CREST AND TOP OF DAM
= $3.5 \times 83.1 = 291 \text{ AC} \cdot \text{FT}$

ESTIMATED STORAGE BELOW SPILLWAY CREST
= $\frac{1}{3} \times 76.7 \times 16 = 409 \text{ AC} \cdot \text{FT}$
(EL. 80 - EL. 64 = 16')

2. MAXIMUM IMPLOYMENT TO TOP OF DAM = 291 + 409 = 700 AC} \cdot \text{FT}

A STAGE-STORAGE CURVE IS PLOTTED (SHEET 2)
THUS, ACCORDING TO CODE OF ENGINEERING GUIDELINES
TABLE 1, THE MILLER POND DAM IS CLASSIFIED SMALL
BASED UPON THE STORAGE CAPACITY OF 700 AC} \cdot \text{FT}.
($< 1000 \text{ AC} \cdot \text{FT} \geq 50$) AND THE HEIGHT OF DAM
IS ONLY 19.5 FT.


HAZARD POTENTIAL — A CLASSIFICATION OF HIGH
HAZARD IS ASSIGNED BASED ON DAM DESIGN ANALYSIS
AND RELATIVE LOCATION OF HOUSES AND OTHER
STRUCTURES DOWNSTREAM OF THE DAM. A
DISCUSSION OF HAZARD POTENTIAL IS INCLUDED
IN THE BREACH ANALYSIS SECTION OF APPENDIX-D.

SHEET 13 OF 19

MA 7/9/80

EB 7/10/80

MILLER POND DAM



STORAGE ABOVE SPILLWAY CREST - AC-FT


PROJECT NON FEDERAL DAM IMPROVEMENT PROJECT NO. 80-10-10 SHEET 4 OF 17
NEW ENGLAND DIVISION COMPUTED BY ME DATE 7/9/80
MILLER ROLL DAM CHECKED BY EB DATE 7/10/80

SELECTION OF TEST FLOOD—

FOR THE SMALL SIZE AND HIGH HAZARD POTENTIAL CLASSIFICATION, TABLE 3 OF CORPS OF ENGINEERS RECOMMENDED GUIDELINES, THE TEST FLOOD COULD BE IN THE $\frac{1}{2}$ PPIF TO PPIF RANGE. BASED ON THE INVOLVED DOWNSTREAM RISK POTENTIAL WHICH IS CONSIDERED TO BE AT THE LOWER END OF THE HIGH HAZARD CLASSIFICATION SCALE A TEST FLOOD $\frac{1}{2}$ PPIF IS SELECTED.

$$\begin{aligned}\text{TEST FLOOD PEAK INFLOW FOR } \frac{1}{2} \text{ PPIF} &= \frac{1}{2} \times 17,200 \text{ CFS} \\ &= \underline{8,610 \text{ CFS}}\end{aligned}$$

NOTE: SURFACE STORAGE ROUTING IS NOT PERFORMED FOR FULL PPIF.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 89-10-10 SHEET 5 OF 19NEW ENGLAND DIVISION COMPUTED BY ME DATE 2-28-91MILLER POND DAM CHECKED BY SP DATE 4/11/91COMPOSITE DISCHARGE RATING CURVEPOTENTIAL OVERFLOW PROFILE

(* HORIZONTAL PROJECTION OF THE LENGTH OF THE DAM NORMAL TO FLOW ON A VERTICAL PLANE)

THE OUTFLOW CAPACITIES OF VARIOUS SECTIONS ARE CALCULATED AND TABULATED ON SHEET 7.

THE SPILLWAY IS OF STONE MASONRY CONSTRUCTION AND OVERFLOW $Q_1 = CLH^{3/2}$, WHERE $C = 2.8$ AND $L = 87.8$ FT. A LOWER VALUE OF C IS CHOSEN BECAUSE OF IRREGULAR FREST CONDITION

THE OVERFLOW CAPACITY OF THE RIGHT EMBANKMENT IS CALCULATED BY $Q_2 = \frac{2}{3} C X L X H^{3/2}$ FOR $C = 2.7$ AND AVERAGE SLOPE OF 1" TO 6.15H, $Q_2 = 11.07 X H^{5/2}$

THE OVERFLOW CAPACITY OF THE DAM IS CALCULATED BY, $Q_3 = C X L X H^{3/2}$, WHERE BECAUSE OF IRREGULAR SHAPE C IS ASSUMED TO BE 2.6 AND THE EFFECTIVE LENGTH OF THE DAM IS 244 FT, AND

DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-10 SHEET 6 OF 19
NEW ENGLAND DIVISION COMPUTED BY MA DATE 4/22/90
MILLER POND DAM CHECKED BY EB DATE 4/29/90

$$\text{THEREFORE } Q_3 = 2.6 \times 244 \times H^{3/2}$$

$$= 634.4 H^{3/2}$$

THE OVERFLOW CAPACITY OF THE LEFT EMBANKMENT IS CALCULATED BY

$$Q_4 = \frac{2}{3} \times C \times L \times H^{3/2},$$

FOR $C = 2.7$ AND AVERAGE SLOPE OF $1V$ TO $5.24H$,

$$Q_4 = 9.43 H^{5/2}.$$

THE OUTFLOW CAPACITY OF THE HIGH-LEVEL OUTLET IS OBTAINED BY $Q_5 = 0.6 \times A \times \sqrt{2gH}$, WHERE $A = 4' \times 4.5'$, INVERT EL. 74.0 AND ELEV. OF CENTER OF THE OUTLET 76.0, $Q_5 = 86.4 \times H^{1/2}$

THE OUTFLOW CAPACITY OF THE LOW-LEVEL OUTLET IS OBTAINED BY $Q_6 = C A \sqrt{2gH}$, WHERE $A = 3' \times 2'$, AND ELEVATION OF THE CENTER OF THE OUTLET IS 65.5 AND $C = 0.6$ ASSUMED


PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-10 SHEET 7 OF 19NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/9/80MILLER POUL DAM CHECKED BY EB DATE 7/10/80TABULATION FOR DISCHARGE RATING CURVE

| ELVN | SPILLWAY $Q_1 = 145.8 H^{3/2}$ $H = 87.5'$ C.ELVN = 80.0 | Q_2 $11.07 \times H^{3/2}$ RT. EMBANKMENT C.ELVN = 80.0 | DAM $Q_3 = 634.4 H^{3/2}$ L-244' C.ELVN = 83.5 | Q_4 $9.43 \times H^{3/2}$ LEFT EMBANKMENT C.ELVN = 83.5 | TOTAL Q CFS |
|------------------------|---|--|---|--|------------------|
| SPICR 78.0 | 0 | 0 | 0 | 0 | 0 |
| 80.0 | 0 | 0 | 0 | 0 | 0 |
| 81.0 | 246 | 11 | 0 | 0 | 257 |
| 82.0 | 695 | 63 | 0 | 0 | 758 |
| 83.0 | 1276 | 173 | 0 | 0 | 1449 |
| DAM CREST 83.5 | 1610 | 254 | 0 | 0 | 1864 |
| 84.0 | 1967 | 334 | 222 | 2 | 2545 |
| 85.0 | 2747 | 619 | 1165 | 26 | 4559 |
| 86.0 | 3613 | 976 | 2508 | 93 | 7190 |
| POOL 6 TEST FLOOD 86.2 | 3795 | 1066 | 2814 | 113 | 7182 |
| 88.0 | 5583 | 2004 | 6056 | 405 | 14,028 |
| PMF 88.48 | 6070 | 2320 | 7055 | 525 | 15,970 |
| 90.0 | 7774 | 3,779 | 10,513 | 1016 | 22,782 |

NOTE: THE TOTAL CAPACITY Q DOES NOT INCLUDE THE DISCHARGE CAPACITY OF THE HIGH-LEVEL OUTLET, BECAUSE OF SMALL QUANTITIES, (FOR POOL 61 TOP OF DAM $Q = 245$ CFS.)

SIMILARLY, THE DISCHARGE CAPACITY OF THE LOW-LEVEL OUTLET Q_4 IS NEGLECTED BECAUSE OF SMALL QUANTITIES (AT TOP OF DAM $Q_4 = 130$ CFS.)

WITH THE ABOVE DATA, DISCHARGE RATING CURVES WERE PLOTTED ON SHEET 8.



MILLER POND DAM
RATING CURVE FOR SPILLWAY AND DAM

Sheet 8 of 19
 E. J. L. A. 4/24/80
 E. J. L. 29-80

| | | | | | | | | | | |
|--------|--------|--------|--------|--------|--------|-------|-------|-------|-------|---|
| 20,000 | 18,000 | 16,000 | 14,000 | 12,000 | 10,000 | 8,000 | 6,000 | 4,000 | 2,000 | 0 |
| | | | | | | | | | | |

PROJECT NONFEDERAL DAM INSPECTION PROJECT NO. 80-10-10 SHEET 91 OF 19
NEW ENGLAND DIVISION COMPUTED BY SP DATE 4/2/80
MILLER POND DAM CHECKED BY SL DATE 4/7/80

DETERMINATION OF PEAK OUTFLOW

FOR $\frac{1}{2}$ PMF TEST FLOOD PEAK INFLOW OF 8610 CFS:

TRIAL #1:

THE PMF HAS 19" OF RUN-OFF FROM DRAINAGE AREA
 $\therefore \frac{1}{2}$ PMF HAS 9.5" OF RUN-OFF FROM THE DRAINAGE AREA.

FOR A DRAINAGE AREA OF 10.5 SQ. MILES
 AND A HEAD OF 3.5 FT

AVAILABLE SURCHARGE STORAGE UP TO TOP OF DAM
 (AVERAGE POND AREA 83.1 ACRES)

$$= \frac{83.1 \times 3.5 \times 12}{10.5 \times 640}$$

= 0.52 INCHES OF
 RUN OFF FROM DRAINAGE
 AREA.

$$\frac{\text{POND SURCHARGE STORAGE}}{\text{INFLOW RUN OFF VOLUME}} = \frac{0.52}{9.5} = 0.055$$

REFERRING TO FIGURE 17-11 "TYPICAL SHORTCUT METHOD
 OF RESERVOIR FLOOD ROUTING" IN SCS NEH SECTION 4
 AUGUST 1972, FOR $\frac{\text{POND SURCHARGE STORAGE}}{\text{INFLOW RUN OFF VOLUME}}$
 OF 0.055 THE GUIDE CURVES GIVES

$$\frac{\text{OUTFLOW PEAK RATE}}{\text{INFLOW PEAK RATE}} = 0.98$$

$$\therefore \text{OUTFLOW PEAK RATE} = 0.98 \times 8610 = 8438 \text{ CFS.}$$

DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-10 SHEET 10 OF 19
NEW ENGLAND DIVISION COMPUTED BY MR DATE 4/29/80
MILLER POND DAM CHECKED BY EB DATE 4/29/80

TRIAL # 2 —

FROM THE COMPOSITE RATING CURVE, THE
 OUTFLOW OF 8438 CFS CORRESPONDS TO EL. 86.4
 ∴ SURCHARGE HEIGHT ABOVE THE SPILLWAY
 CREST (EL. 80.0) = 6.4 FT.

POND AREA IS 100 ACRES AT EL. 86.4
 AVERAGE POND AREA 88.35 ACRES

VOLUME OF SURCHARGE STORAGE (STOR) = $\frac{88.35 \times 6.4}{10.5 \times 640} \times 12 = 1.01$ OF
 DRAINAGE AREA

$$\begin{aligned} \text{PEAK OUTFLOW } Q_p &= Q_p \left(1 - \frac{\text{STOR}}{9.5}\right) \\ &= 8610 \left(1 - \frac{1.01}{9.5}\right) \\ &= 7695 \text{ CFS.} \end{aligned}$$

TRIAL # 3 —

FROM THE COMPOSITE RATING CURVE, THE OUTFLOW
 OF 7695 CFS CORRESPONDS TO EL. 86.2
 SURCHARGE HEIGHT ABOVE SPILLWAY CREST (EL. 80.0)
 = 6.2 FT

POND AREA IS 99.4 ACRES @ EL. 86.2
 VOLUME OF SURCHARGE STORAGE = $\frac{8805 \times 6.2}{10.5 \times 640} \times 12 = 0.97$ INCHES
 (AVERAGE LAKE AREA 88.05 ACRES) OF DRAINAGE AREA.

$$\begin{aligned} \therefore \text{PEAK OUTFLOW } Q_p &= 8610 \left(1 - \frac{0.97}{9.5}\right) \\ &= 7730 \text{ CFS.}^* \end{aligned}$$

THIS OUTFLOW CORRESPONDS TO A MAXIMUM
 POOL ELEVATION = 86.2

∴ MAXIMUM SURCHARGE HEIGHT ABOVE SPILLWAY
 CREST (EL. 80.0) = 6.2 FT.

* THIS WAS CHECKED USING THE CORPS OF ENGINEERS
 "MODELING SURCHARGE STORAGE ROUTING" ALTERNATE
 METHOD

PROJECT NON-FEDERAL DAM INSPECTION PROJECT NO. 8.3-10-10 SHEET 11 OF 19
NEW ENGLAND DIVISION COMPUTED BY MA DATE 4/28/80
MILLER POOL DAM CHECKED BY EB DATE 4/29/80

NON-OVERFLOW SECTION OF THE DAM WOULD BE
OVERTOPPED BY 2.7 FT.

(THE DIFFERENCE IN EL. 86.2 AND EL. 83.5)

THE CAPACITY OF THE SPILLWAY AT MAXIMUM POOL
IS A PERCENT OF ROUTED TEST FLOOD OUTFLOW

$$\frac{373.5}{7730} = 4.9\%$$

AND CAPACITY OF THE SPILLWAY TO TOP OF DAM
AS A PERCENT OF TEST FLOOD OUTFLOW

$$\frac{1610}{7730} = 2.1\%$$

DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-10 SHEET 12 OF 19
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/9/80
MILLER POND DAM CHECKED BY EB DATE 7/12/80

ROUTING IS ALSO TO BE MADE

DETERMINATION OF PEAK OUTFLOW
FOR PMF PEAK INFLOW OF 17,220 CFS

TRIAL #1

THE PMF HAS 19" OF RUN OFF FROM DRAINAGE AREA
AVAILABLE SURCHARGE STORAGE UP TO TOP OF DAM

= 0.52 INCHES OF RUN OFF FROM
DRAINAGE AREA

$$\frac{\text{POND SURCHARGE STORAGE}}{\text{INFLOW RUN OFF VOLUME}} = \frac{0.52}{19} = 0.03$$

REFERRING TO FIGURE 17-1 "TYPICAL SHEPHERD METHOD
OF RESERVOIR FLOOD ROUTING" IN SEC. 17.4 SECTION 4
AUGUST 1972

FOR 0.03 THE CURVE GIVES

$$\frac{\text{PEAK INFLOW}}{\text{INFLOW PEAK RATE}} = 0.77$$

$$\text{OUTFLOW PEAK RATE} = 0.99 \times 17,220$$

$$= 17,047.8 \text{ CFS}$$

TRIAL #2

FROM THE CURVE TABLE FOR THE OUTFLOW OF
17,000 CFS CORRESPONDING TO 0.03

SURCHARGE HEIGHT ABOVE THE DAM IS
0.17 FT.

POND AREA AT 0.17 FT. = 108.5 ACRES
AREAS 1.00 FT. = 72.6 ACRES

PROJECT NO. F. 2381-1001-10-11 PROJECT NO. 60-10-10 SHEET 13 OF 19
NEW BRIDGE ON RIVER COMPUTED BY ES DATE 1/9/80
CHIEF ENGINEER CHECKED BY ES DATE 2/12/80

VOLUME OF SURCHARGE STORAGE (STOR.)

$$\frac{92.1 \times 8.7}{10.5 \times 640} \times 12 = 1.44'' \text{ OF D.A.}$$

$$\text{PEAK OUTFLOW } Q_P = Q_P \left(1 - \frac{\text{STOR.}}{19}\right) = 17,220 \left(1 - \frac{1.44}{19}\right) \approx 15,970 \text{ CFS}$$

TRIAL #3.

FROM THE RATING CURVE, THE OUTFLOW OF 15,970 CFS CORRESPONDS TO 22.88 FT.

SURCHARGE HEIGHT ABOVE SPILLWAY CREST (22.80) = 8.45 FT.

POOL AREA AT 22.88 FT. = 107.15 ACRES.

VOLUME OF SURCHARGE STORAGE (STOR.) = $\frac{92 \times 8.4 \times 12}{10.5 \times 640} = 1.38''$
 (AVERAGE POOL AREA ≈ 92 ACRES) OF D.A.

$$\therefore \text{PEAK OUTFLOW } Q_P = 17,220 \left(1 - \frac{1.38}{19}\right) \approx 15,970 \text{ CFS}$$

THIS OUTFLOW CORRESPONDS TO A MAXIMUM POOL ELEVATION = 22.88 FT.

\therefore MAXIMUM SURCHARGE HEIGHT ABOVE SPILLWAY CREST (22.80) = 6.45 FT

NON-OVERFLOW SECTION OF THE DAM IS NOT OVERFLOWED BY (THE DIFFERENCE IN 22.88 FT. AND 22.80 FT.) = 4.98 FT.

THE CAPACITY OF THE SPILLWAY TO MAXIMUM POOL AREA % OF PMF PEAK FLOOD OUTFLOW = $\frac{6070}{15,970} = 38\%$

AND CAPACITY OF THE SPILLWAY TO TOP OF DAM AS A PERCENT OF PMF PEAK FLOOD OUTFLOW

$$\frac{1610}{15,970} = 1\%$$

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-10 SHEET 14 OF 19

NEW ENGLAND DIVISION COMPUTED BY MR DATE 1/29/80

MILLER POND DAM CHECKED BY EL DATE 2/3/80

BREACH ANALYSIS

DOWNSTREAM FAILURE HAZARD -

PEAK FLOOD AND STAGE IMMEDIATELY DOWNSTREAM
FROM DAM PER CORPS OF ENGINEERS DAM FAILURE
GUIDELINES -

BREACH OUTFLOW

$$Q_b = \frac{8}{27} W_b \sqrt{g} y_o^{3/2}$$

BREACH WIDTH W_b :

THE EFFECTIVE LENGTH OF THE DAM AT MID-HEIGHT = 173 FT.
40% OF 173 = 69.2 FT. USE $W_b = 69$ FT.

y_o : USING POOL ELEVATION AT TOP OF DAM (EL. 83.5) TO
COMPUTE PEAK FAILURE OUTFLOW. HEIGHT AT TIME
OF FAILURE IS DIFFERENCE BETWEEN EL. 83.5
AND EL. 64.0

$$y_o = 19.5 \text{ FT}$$

$$\text{BREACH OUTFLOW } Q_b = \frac{8}{27} \times 69 \times \sqrt{32.2} \times (19.5)^{3/2} \\ \approx 10,000 \text{ CFS}$$

FOR POOL AT TOP OF DAM -

SPILLWAY FLOW PRIOR TO FAILURE = 1615 CFS

FLOW OVER THE RIGHT SLOPE PRIOR

TO FAILURE = 254 CFS

TOTAL PEAK FAILURE OUTFLOW $Q_P = 10,000 + 1615 + 254 = 11,864 \text{ CFS}$
SAY, 12,000 CFS.

ESTIMATED FAILURE FLOOD DEPTH $\approx 2 \frac{1}{2}$ Y

IMMEDIATELY FROM DAM $\approx 1 \frac{1}{2} \times 10 = 15 \text{ FT}$

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-10 SHEET 15 OF 19
NEW ENGLAND DESIGN COMPUTED BY MD DATE 7/9/80
MILLER ROAD DAM CHECKED BY SL DATE 7/10/80

FLOOD STAGE AND DEPTH D/S REACHES


AN EXAMINATION OF THE D/S CONDITIONS INDICATES THAT THE MAJORITY OF THE POTENTIAL FLOOD FLOW REACH IS QUITE NARROW AND STEEP; THEREFORE A VERY SMALL QUANTITY OF FLOOD VOLUME WOULD BE STORED. HENCE, THE FOLLOWING ANALYSIS IS BASED ON THE ASSUMPTION THAT NO ATTENUATION OF THE FLOOD VOLUME TAKES PLACE IN THE D/S REACHES OF THE DAM.

INITIAL IMPACT AREA (BLOOMINGDALE RD. VICINITY) —
 BY USING MANNING'S EQUATION —

$$Q = A \times \frac{1.486}{n} (R)^{4/3} \times (S)^{1/2}$$

THE BED SLOPE S IS DETERMINED FROM USGS QUADRANGLE MAP — 1" DROP IN ELEVATION OF 1011 IN 3480 FT.


$$\therefore S = 0.0029$$



FROM AN OBSERVATION OF THE SITE AS WELL AS USGS MAP, THE SLOPES OF BOTH SIDES OF THE CHANNEL ARE ASSUMED TO BE 1 V TO 12 H

$$A = 12 H^2, \quad P = H \sqrt{145} + H \sqrt{145} = 24.08 H$$

$$R = \frac{A}{P} = \frac{12 H^2}{24.08 H} = 0.498 H$$



IN MANNING'S EQUATION —

FOR TOTAL PEAK FAILURE OUTFLOW OF 12,000 CFS AND $n = 0.025$ —

$$12,000 = \frac{12 H^2 \times 1.486 \times (0.498 H)^{4/3} \times (0.0029)^{1/2}}{0.025}$$

$$= 24.14 H^{8/3}$$

FLOOD DEPTH H CORRESPONDING TO $Q = 12,000$ CFS
 BLOOMINGDALE ROAD

AND FLOOD STAGE ≈ 61.5 (APPROXIMATE) (EL. 51.5)
 SIMILARLY, USING THE ABOVE PROCEDURES, FOR

DIVERSIFIED TECHNOLOGIES CORP.

CONSULTING ENGINEERS
NORTH HAVEN, CONN.

PROJECT NONFEDERAL DAM INSPECTION PROJECT NO. 80-10-10 SHEET 16 OF 19

NEW SUBSIDY DIVISION

COMPUTED BY MR

DATE 4-17-60

MILLER POND DAM

CHECKED BY


DATE 7/3/60

PREFAILURE FLOW 1864 CFS,
PREFAILURE FLOOD DEPTH = 5.1 FT
AND PREFAILURE STAGE = 56.3

THUS, THE RAISE IN STAGE AFTER DAM FAILURE
AT INITIAL IMPACT AREA

$$\Delta y_1 = 61.5 - 56.3 = \underline{5.2 \text{ FT}}$$

AT THIS IMPACT AREA THERE IS A CULVERT
CONSISTING OF THREE 72" CONCRETE PIPES AND
ITS CAPACITY IS EXAMINED
WITH FULL FLOW AND FREE
OUTFALL CONDITIONS;



FOR INLET CONTROL $\frac{\text{HEADLAYER HW}}{\text{DIAMETER } d} = \frac{4.00}{6.0}$

$$= 1.5$$

AND USING U.S. BUREAU OF PUBLIC ROADS
JANUARY '63 NOMOGRAPH FOR HEADLAYER SCALE
NO. 2, REVISED MAY 1964,

DISCHARGE THROUGH EACH PIPE = 350 CFS.
THUS, UNDER THE ABOVE CONDITIONS TOTAL
DISCHARGE THROUGH ALL THE THREE PIPES = $3 \times 350 = 1050$
CFS, WHICH IS ONLY 9% OF THE TOTAL PEAK
FAILURE OUTFLOW OF 12,000 CFS.

THE HOUSE ADJACENT TO THE BROOK ADJACENT TO
BLOOMINGDALE ROAD IS APPROXIMATELY 2 FT. ABOVE
THE CHANNEL BED. SINCE THE FLOOD DEPTH AT
DAM FAILURE IS ESTIMATED TO BE 10.3 FT, THE
1ST FLOOR OF THE HOUSE WILL BE FLOODED
BY $2.3 \pm$ FT OF WATER. THE SITUATION WOULD
BE FURTHER AGGRAVATED BECAUSE OF
THE INADEQUATE CAPACITY OF THE CULVERT.


PROJECT NONFEDERAL DAM INSPECTION PROJECT NO. 80-16 16 SHEET 17 OF 19
NEW ENGLAND DIVISION COMPUTED BY MP DATE 4/29/80
MILLER D. J. CHECKED BY ED DATE 4/1/80

TWO ADDITIONAL HOMES SOUTH OF THE BROOK WOULD BE SIMILARLY IMPACTED WITH $2 \pm$ FT OF FLOOD WATER.

SECONDARY IMPACT AREA (OLD NORWICH ROAD)

THE CHANNEL BED SLOPE, S IS DETERMINED BY FIELD INFORMATION AND USGS MAP - $S = 0.0093$

FROM AN OBSERVATION OF THE SITE AND AN EXAMINATION OF USGS MAP, THE SLOPES OF BOTH SIDES OF THE CHANNEL ARE ASSUMED TO BE 1^V TO 8^H



USING MANNING'S EQUATION

$$Q = A \times 1.486 (R)^{4/3} (S)^{1/2}$$

$$A = 8H^2, P = 4\sqrt{65} + 4\sqrt{65} = 16.12H$$

$$R = \frac{A}{P} = \frac{8H^2}{16.12H} = 0.496H$$

FOR TOTAL PEAK FAILURE OUTFLOW OF 12,000 CFS
 AREA $T = 10.5$

$$12,000 = 8H^2 \times \frac{1.486}{0.025} \times (0.496H)^{4/3} \times (0.0093)^{1/2}$$

$$= 28.72 H^{8/3}$$

\therefore FLOOD DEPTH JUST PRIOR TO REACHING

OLD NORWICH ROAD $\cong 9.6$ FT.

AND FLOOD STAGE $\cong 12.6$ (APPROXIMATE CHANNEL VELOCITY)

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-10 SHEET 18 OF 19

NEW ENGLAND DIVISION COMPUTED BY MP DATE 11/24/80

MILLER POND DAM CHECKED BY E6 DATE 4/2/80


SIMILARLY, USING THE ABOVE PROCEDURE, FOR A
PREFAILURE FLOW OF 1864 CFS,

PREFAILURE FLOOD DEPTH = 4.8 FT.
AND PREFAILURE STAGE = 7.8

AND THE RAISE IN STAGE AFTER DAM FAILURE AT
SECONDARY IMPACT AREA $\Delta y = 12.6 - 7.8 = 4.8$ FT

AT THIS IMPACT AREA THERE IS A 120" CULVERT AND
ITS CAPACITY IS EXAMINED SIMILARLY AS THE CULVERT
ON INITIAL IMPACT AREA WITH $\frac{H_w}{d} = \frac{120}{120} = 1$

AND $Q = 800$ CFS WHICH IS ONLY
7% OF THE TOTAL PEAK
FAILURE OUTFLOW OF 12,000 CFS.



THE BUILDING ADJACENT TO
THE CULVERT AND CONTAINING SEVERAL BUSINESSES,
IS 3'± BELOW THE FLOOD AND THEREFORE WILL
BE FLOODED BY 2.6± FEET OF WATER. A PORTION OF OLD NORWICH
RD, WHICH IS A WELL TRAVELED ROADWAY WOULD
BE SUBMERGED AND IT IS LIKELY THAT
TWO DWELLINGS ADJACENT TO THIS CULVERT
WOULD ALSO BE INUNDATED WITH 2± FEET OF
FLOOD WATER.

THUS, THE PEAK FAILURE OUTFLOW WOULD RESULT IN FLOOD
OF A MAGNITUDE THAT WOULD IMPACT AT LEAST FIVE
HOUSES, A BUILDING CONTAINING SEVERAL BUSINESSES AND
THREE CULVERTS. IT IS REPORTED THAT ONE OF THESE
CULVERTS IS 2200± FT. D/S OF THE DAM WAS WASHED OUT
DUE TO A RECENT FLOODING.

BASED ON THIS ANALYSIS A DAMAGED CULVERT OF SUCH
MAGNITUDE IS CONSIDERED LIKELY.

PROJECT NON FEDERAL DAM INSPECTION PROJECT NO. 80-10-10 SHEET 19 OF 19
NEW ENGLAND DIVISION COMPUTED BY MA DATE 7/10/80
MILLER POND DAM CHECKED BY EB DATE 7/10/80

SUMMARY - HYDRAULIC/HYDROLOGIC COMPUTATIONS

TEST FLOOD PEAK INFLOW $\frac{1}{2}$ PMF 8610 CFS

(Parallel Computations Have been Performed for PMF Peak Inflow and results are summarized below)

| <u>PERFORMANCE AT PEAK FLOOD CONDITIONS:</u> | <u>$\frac{1}{2}$ PMF</u> | <u>PMF</u> |
|---|-------------------------------------|------------|
| PEAK INFLOW CFS | 8610 | 17,220 |
| PEAK OUTFLOW CFS | 7730 | 15,970 |
| SPILL CAP TO TOP OF DAM (EL. 83.5 NGVD) CFS | 1610 | 1,610 |
| SPILL CAP TO TOP OF DAM % OF PEAK OUTFLOW | 21 | 10 |
| SPILL CAP TO PEAK FLOOD ELVN. CFS | 3,795 | 6,070 |
| SPILL CAP TO PEAK FLOOD ELVN. % OF PEAK OUTFLOW | 49 | 38 |

PERFORMANCE:

| | | |
|---|------|-----------|
| MAX. POOL ELEVATION NGVD | 86.2 | 88.48 |
| MAX. SURCHARGE HEIGHT ABOVE SPILL CREST FT. | 6.2 | 8.5 \pm |
| NON-OVERFLOW SECTION OF THE DAM OVERTOPPED FT | 2.7 | 5 \pm |

DOWNSTREAM FAILURE CONDITIONS:

| | |
|--------------------------------------|--------|
| PEAK FAILURE OUTFLOW CFS | 12,000 |
| FLOOD DEPTH IMMEDIATELY D/S FROM DAM | 13 FT. |

CONDITIONS AT THE INITIAL IMPACT AREA:

| | |
|---|-----------|
| ESTIMATED STAGE BEFORE FAILURE WITH 1864 CFS | 56.3 NGVD |
| ESTIMATED STAGE AFTER FAILURE WITH 12,000 CFS | 61.5 NGVD |
| ESTIMATED RAISE IN STAGE AFTER FAILURE Δy_1 | 5.2 FT. |

CONDITIONS AT THE SECONDARY IMPACT AREA:

| | |
|---|-----------|
| ESTIMATED STAGE BEFORE FAILURE WITH 1864 CFS | 7.8 NGVD |
| ESTIMATED STAGE AFTER FAILURE WITH 12,000 CFS | 12.6 NGVD |
| ESTIMATED RAISE IN STAGE AFTER FAILURE Δy_2 | 4.8 FT. |

PRELIMINARY GUIDANCE
FOR ESTIMATING
MAXIMUM PROBABLE DISCHARGES
IN
PHASE I DAM SAFETY
INVESTIGATIONS

New England Division
Corps of Engineers

March 1978


MAXIMUM PROBABLE FLOOD INFLOWS
NED RESERVOIRS

| <u>Project</u> | <u>Q</u> (cfs) | <u>D.A.</u> (sq. mi.) | <u>MPF</u> cfs/sq. mi. |
|-----------------------|-------------------|--------------------------|---------------------------|
| 1. Hall Meadow Brook | 26,600 | 17.2 | 1,546 |
| 2. East Branch | 15,500 | 9.25 | 1,675 |
| 3. Thomaston | 158,000 | 97.2 | 1,625 |
| 4. Northfield Brook | 9,000 | 5.7 | 1,580 |
| 5. Black Rock | 35,000 | 20.4 | 1,715 |
| 6. Hancock Brook | 20,700 | 12.0 | 1,725 |
| 7. Hop Brook | 26,400 | 16.4 | 1,610 |
| 8. Tully | 47,000 | 50.0 | 940 |
| 9. Barre Falls | 61,000 | 55.0 | 1,109 |
| 10. Conant Brook | 11,900 | 7.8 | 1,525 |
| 11. Knightville | 160,000 | 162.0 | 987 |
| 12. Littleville | 98,000 | 52.3 | 1,870 |
| 13. Colebrook River | 165,000 | 118.0 | 1,400 |
| 14. Mad River | 30,000 | 18.2 | 1,650 |
| 15. Sucker Brook | 6,500 | 3.43 | 1,895 |
| 16. Union Village | 110,000 | 126.0 | 873 |
| 17. North Hartland | 199,000 | 220.0 | 904 |
| 18. North Springfield | 157,000 | 158.0 | 994 |
| 19. Ball Mountain | 190,000 | 172.0 | 1,105 |
| 20. Townshend | 228,000 | 106.0(278 total) | 820 |
| 21. Surry Mountain | 63,000 | 100.0 | 630 |
| 22. Otter Brook | 45,000 | 47.0 | 957 |
| 23. Birch Hill | 88,500 | 175.0 | 505 |
| 24. East Brimfield | 73,900 | 67.5 | 1,095 |
| 25. Westville | 38,400 | 99.5(32 net) | 1,200 |
| 26. West Thompson | 85,000 | 173.5(74 net) | 1,150 |
| 27. Hodges Village | 35,600 | 31.1 | 1,145 |
| 28. Buffumville | 36,500 | 26.5 | 1,377 |
| 29. Mansfield Hollow | 125,000 | 159.0 | 786 |
| 30. West Hill | 26,000 | 28.0 | 928 |
| 31. Franklin Falls | 210,000 | 1000.0 | 210 |
| 32. Blackwater | 66,500 | 128.0 | 520 |
| 33. Hopkinton | 135,000 | 426.0 | 316 |
| 34. Everett | 68,000 | 64.0 | 1,062 |
| 35. MacDowell | 36,300 | 44.0 | 825 |

MAXIMUM PROBABLE FLOWS
BASED ON TWICE THE
STANDARD PROJECT FLOOD
(Flat and Coastal Areas)

| <u>River</u> | <u>SPF</u> (cfs) | <u>D.A.</u> (sq. mi.) | <u>MPF</u> (cfs/sq. mi.) |
|-------------------------|---------------------|--------------------------|-----------------------------|
| 1. Pawtuxet River | 19,000 | 200 | 190 |
| 2. Mill River (R.I.) | 8,500 | 34 | 500 |
| 3. Peters River (R.I.) | 3,200 | 13 | 490 |
| 4. Kettle Brook | 8,000 | 30 | 530 |
| 5. Sudbury River. | 11,700 | 86 | 270 |
| 6. Indian Brook (Hopk.) | 1,000 | 5.9 | 340 |
| 7. Charles River. | 6,000 | 184 | 65 |
| 8. Blackstone River. | 43,000 | 416 | 200 |
| 9. Quinebaug River | 55,000 | 331 | 330 |

ESTIMATING EFFECT OF SURCHARGE STORAGE ON MAXIMUM PROBABLE DISCHARGES



STEP 1: Determine Peak Inflow (Q_{p1}) from Guide Curves.

STEP 2: a. Determine Surcharge Height To Pass " Q_{p1} ".

b. Determine Volume of Surcharge ($STOR_1$) In Inches of Runoff.

c. Maximum Probable Flood Runoff In New England equals Approx. 19", Therefore:

$$Q_{p2} = Q_{p1} \times \left(1 - \frac{STOR_1}{19}\right)$$


STEP 3: a. Determine Surcharge Height and " $STOR_2$ " To Pass " Q_{p2} "

b. Average " $STOR_1$ " and " $STOR_2$ " and Determine Average Surcharge and Resulting Peak Outflow " Q_{p3} ".

MAXIMUM PROBABLE FLOOD PEAK FLOW RATES

x 5 - NED DAM IDENTIFICATION

⊗ 7' - TWICE SPF AT INDICATED SITES
DEC. 1977



SURCHARGE STORAGE ROUTING SUPPLEMENT

STEP 3: a. Determine Surcharge Height and
"STOR₂" To Pass "Q_{p2}"

b. Avg "STOR₁" and "STOR₂" and
Compute "Q_{p3}".

c. If Surcharge Height for Q_{p3} and
"STOR_{AVG}" agree O.K. If Not:

STEP 4: a. Determine Surcharge Height and
"STOR₃" To Pass "Q_{p3}"

b. Avg. "Old STOR_{AVG}" and "STOR₃"
and Compute "Q_{p4}"

c. Surcharge Height for Q_{p4} and
"New STOR_{AVG}" should Agree
closely

SURCHARGE STORAGE ROUTING ALTERNATE

$$Q_{p2} = Q_{p1} \times \left(1 - \frac{\text{STOR}}{19} \right)$$


$$Q_{p2} = Q_{p1} - Q_{p1} \left(\frac{\text{STOR}}{19} \right)$$

FOR KNOWN Q_{p1} AND 19" R.O.


Q_{p2}

STOR

EL.



"RULE OF THUMB" GUIDANCE FOR ESTIMATING DOWNSTREAM DAM FAILURE HYDROGRAPHS



STEP 1: DETERMINE OR ESTIMATE RESERVOIR STORAGE (S) IN AC-FT AT TIME OF FAILURE.

STEP 2: DETERMINE PEAK FAILURE OUTFLOW (Q_{p1}).

$$Q_{p1} = \frac{8}{27} W_b \sqrt{g} Y_o^{3/2}$$

W_b = BREACH WIDTH - SUGGEST VALUE NOT GREATER THAN 40% OF DAM LENGTH ACROSS RIVER AT MID HEIGHT.

Y_o = TOTAL HEIGHT FROM RIVER BED TO POOL LEVEL AT FAILURE.

STEP 3: USING USGS TOPO OR OTHER DATA, DEVELOP REPRESENTATIVE STAGE-DISCHARGE RATING FOR SELECTED DOWNSTREAM RIVER REACH.

STEP 4: ESTIMATE REACH OUTFLOW (Q_{p2}) USING FOLLOWING ITERATION.

A. APPLY Q_{p1} TO STAGE RATING, DETERMINE STAGE AND ACCOMPANYING VOLUME (V_1) IN REACH IN AC-FT. (NOTE: IF V_1 EXCEEDS $1/2$ OF S, SELECT SHORTER REACH.)

B. DETERMINE TRIAL Q_{p2} .

$$Q_{p2}(\text{TRIAL}) = Q_{p1} \left(1 - \frac{V_1}{S}\right)$$

C. COMPUTE V_2 USING Q_{p2} (TRIAL).

D. AVERAGE V_1 AND V_2 AND COMPUTE Q_{p2} .

$$Q_{p2} = Q_{p1} \left(1 - \frac{V_{\text{avg}}}{S}\right)$$

STEP 5: FOR SUCCEEDING REACHES REPEAT STEPS 3 AND 4.

APRIL 1978

APPENDIX E

INFORMATION AS CONTAINED IN
THE NATIONAL INVENTORY OF DAMS

END

FILMED

8-84

DTIC